

Owner: City of Chilliwack
Location: Evans Road Crossing of Luckakuck Road, Highway 1, Chilliwack Creek, and Diversion, Chilliwack, British Columbia
Coordinates: 49°08'41"N, 121°58'40"W
Market: Bridge Structures (Design-Build)
Start / Completion Dates: August 2008 – October 2009
Contract Value: CDN \$6,600,000

**Project Description:**

The Evans Road Connector Project provided a much-needed north-south link between residential, commercial, and industrial areas in the City of Chilliwack.

Delivered through a design-build contract, the new road system makes use of round-a-bouts and a new eastbound off-ramp from the Trans-Canada Highway to greatly increase traffic flow, easing demand on the other adjacent interchanges.



Corporate Role:

Working as a subcontractor to Martens Asphalt, the DB Contractor, Coquitlam Ridge Constructors provided construction services for the completion of four new bridge structures, MSE wall-top moment barriers, retaining walls, slope paving, installation of suspended utilities, and coordination of in-stream pile driving by a local subcontractor.

All four bridge structures can carry up to four lanes of traffic with cycling and pedestrian accommodations. Designs for all bridge structures consist of cast-in-place concrete with pre-stressed pre-cast concrete box beams.

Project Reference: Mr. Frank Van Nynatten, ASCT – City of Chilliwack Tel. 604-793-2954